






| DATE | REV | DESCRIPTION | BY | CHKD |
|------|-----|-------------|----|------|
|      | A/0 |             |    |      |
|      |     |             |    |      |
|      |     |             |    |      |



| Conductor       |              | Insulation |           |           | Jacket    | Overall diameter |
|-----------------|--------------|------------|-----------|-----------|-----------|------------------|
| MM <sup>2</sup> | Construction | Diamete    | Min.Thick | AVG.Ghick | Min.Thick |                  |
| 1.0             | 32/0.19mm    | 2.5±0.05mm | 0.44mm    | 0.6mm     | 0.58mm    | 7.0±0.1mm        |



NOTES:

1. PLUG: SF-03+SF-82
2. WIRE: H05VV-F 3G1.0MM<sup>2</sup>
3. COLOR: IV017 (牙017)
4. LENGTH: 2500±20mm

ROHS.compliant

Unless specified on the drawing, tolerances are per the follows:  
. ± 1  
.X ± 0.2  
.XX ± 0.05



|            |          |          |        |      |  |
|------------|----------|----------|--------|------|--|
| DRAW.NO    | SF-03+82 | ITEM     | AK5011 |      |  |
| DEPARTMENT | R&D      | DRAW     | LCH    | DATE |  |
| SCALE      |          | CHECKER  |        | DATE |  |
| UNIT       | MM       | APPROVAL |        | DATE |  |

3RD

